

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25454-00-00
Spot: W2SESE Sec/Twnshp/Rge: 11-11S-18W
670 feet from S Section Line, 990 feet from E Section Line
Lease Name: CARMICHAEL Well #: 8
County: ELLIS Total Vertical Depth: 3450 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	238	0	150 SX
PROD	5.5	3450	0	500 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2011 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: GERARD HOLINDE Company: NOBLE ENERGY, INC. Phone: (785) 639-6302

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Noble Energy milled on hole - got to 869' - broke through casing and was loosing the hole.
Alt II completed.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2011 11:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Basic Energy rigged to 5 1/2" casing and pumped 100 sxs 60/40 pozmix neat - followed with 200 sxs cement with 400# hulls mixed in.
Filled 8 5/8" casing and 5 1/2" casing.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:


Top	Bot	Thru	Comments
3374	3380		

Remarks: BASIC ENERGY SERVICES, LP-TICKET #4715-A.

Plugged through: CSG

District: 04

Signed _____



(TECHNICIAN)

CM

RECEIVED
AUG 19 2011
KCC WICHITA

Form CP-28
8/23/11

AUG 15 2011