

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05256-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 15-11S-18W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PEAVEY A Well #: 2
County: ELLIS Total Vertical Depth: 3330 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W RD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	134	0	w/unknown sxs cmt
PROD	5.5	3495	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2011 2:30 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: WILLIAM F. BOWMAN Company: THE BILL BOWMAN OIL COMPAN Phone: (785) 885-4830

Proposed 08/15/2011 - Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plugging 08/16/2011 - Ordered additional 300 sxs 60/40 pozmix - 600# hulls.
Method: Got to 3250' - hit iron.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2011 9:50 AM KCC Agent: PAT STAAB

Actual Plugging Report:


08/15/2011 - Bowman Oil Company RIH with tubing to 3250'.
Swift Services rigged to tubing and pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1700'. Swift rigged to tubing and pumped 100 sxs cement with 150# hulls mixed in.
Pulled tubing to 850'. Swift rigged to tubing and pumped 150 sxs cement with 150# hulls mixed in - no circulation.
Pulled tubing - shut down for the night.
08/16/2011 - RIH with tubing to 1175' - tagged cement.
Swift rigged to tubing and pumped 100 sxs cement with 225# hulls mixed in to circulate cement to surface.
Pulled tubing. Topped off 5 1/2" casing with 25 sxs cement - hole standing full.

Perfs:

Remarks: SWIFT SERVICES, INC.-TICKET #19748.

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

RECEIVED
AUG 22 2011
KCC WICHITA
Form CP-2/3
8/23/11
CM

AUG 18 2011