

8-19-87

API NUMBER 15- 051-21,678 -00-00

To: 6 070583
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW NE, SEC. 8, T 14 S, R 19 (W/D)

TECHNICIAN'S PLUGGING REPORT
4687

_____ feet from S section line
_____ feet from E section line

Operator License # _____

Lease Name Kinderknecht Well # B #8

Operator: Lasmo Energy Corp
Name & Address: P. O. Box 1365
Great Bend, Kansas 67530

County Ellis 125.48

Well Total Depth 3861 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B. J. Titan License Number _____

Address Box 69 Hays, Kansas 67601

Company to plug at: Hour: 11:30 AM Day: 19 Month: August Year: 19 87

Plugging proposal received from Buster Humphrey

(company name) Lasmo Energy Corp (phone) 316-792-2585

were: 8 5/8" 261' S.P. cwc w/261 sks cmt. 4 1/2" csg set at 3849' w/200 sks cmt.

No perms. * Open hole, D.V. tool at 1524' w/200 sks cmt. No pipe rec.

Proposal 200 sks 65/35 Pozmix 10% Gel 3% Ca Cl and 5 sks Hulls.

Pump in with pump truck, load and pressure annulus with cement, load and pressure 4 1/2" csg with cmt.

Plugging Proposal Received by MSJ
(TECHNICIAN)
Marion J. Schmidt

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:35 PM Day: 19 Month: August Year: 19 87

ACTUAL PLUGGING REPORT Ordered 200 sks 65/35 Pozmix 10% Gel 3% Ca Cl and 5 sks Hulls.

Pumped in with pump truck. Pumped in annulus 2 sks cmt. Max Psig. 800#.

Shut in at 600 Psig. Pumped in 4 1/2" csg 10 sks cmt, 4 sks Hulls and 110 sks cmt. w/1 sk Hulls added in. Max pressure 1700 Psig. Shut in at 1000 Psig. Cmt by B. J. Titan.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

9-1-87

INVOICED observe this plugging.

DATE 9-3-87

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

INV. NO. 18000

8-19