

15-159-28198-00-01

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: ~~15-159-28198-00-01~~  
Spot: SESESE Sec/Twnshp/Rge: 14-185-SW  
330 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: COLBERG Well Number: 1  
County: RICE Total Vertical Depth: 3230 feet

Operator License No.: 8917  
Op Name: GUSTUS DEAN DBA JD PRODUCTION  
Address: 701 MAIN  
GENESEO, KS 67444

Production Casing Size: 5.5 feet: 3152  
Surface Casing Size: 8.625 feet: 250

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/10/2003 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.  
RECEIVED  
KCC DISTRICT #9  
SEP 15 2003

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/10/2003 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sand perfs to 2640' and put 5 sacks cement on top. Perforate 5-1/2" at 1100', 750', and 300'. Run tubing to 1100' and pump 35 sacks with 100 lbs cotton hulls. Pull tubing to 750' and pump 35 sacks with 100 lbs cotton hulls. Pull tubing to 300' and circulate cement to surface with cotton hulls.

Remarks: ALLIED CEMENT TICKET #12761 60/40 POZ. 4% GEL  
Plugged through: TBG

District: 02 Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
AUG 25 2011  
8-25-11  
KCC WICHITA