

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-20755-00-00  
Spot: SWNW Sec/Twnshp/Rge: 19-27S-15W  
1997 feet from N Section Line, 645 feet from W Section Line  
Lease Name: FRUIT Well #: 1  
County: PRATT Total Vertical Depth: 4650 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 155 N MARKET STE 700  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	310		WITH 200 SX CMT
PROD	4.5	4649	2230	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2011 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: PAT LIVINGSTON Company: VINCENT OIL Phone: (620) 388-6143

Proposed Plugging Method: SAND TO 4470' WITH 4 SX CMT. PLUG AT 1000' WITH 12 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2011 3:40 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4470' WITH 4 SX CMT. 1ST PLUG AT 1000' WITH 12 SX GEL, 100# HULLS & 50 SX CMT. 2ND PLUG AT 340' WITH 100# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4522	4528		

RECEIVED  
AUG 23 2011  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
AUG 19 2011  
KCC DODGE CITY

Form CP 2/3