

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22798-00-00  
Spot: W2W2NW Sec/Twnshp/Rge: 21-24S-13W  
1365 feet from N Section Line, 298 feet from W Section Line  
Lease Name: BECKERDITE Well #: 1  
County: STAFFORD Total Vertical Depth: 4107 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3690		WITH 2 SX CMT
SURF	8.625	240		WITH 165 SX CMT
PLG	5.5	4084		
PROD	5.5	4106	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2011 8:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: SET CIBP @ 3738' WITH 2 SX CMT. PERFORATE @ 770'. RUN TBG TO 780'. CIRCULATE CMT UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2011 11:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*TBG FISH @ 3740\*\* TAGGED FISH @ 3702'. SET CIBP @ 3690' & BAILED 2 SX CMT ON TOP OF PLUG. PERFORATED 5 1/2" @ 770'. RAN TBG TO 806'. PUMPED 190 SX CMT DOWN THE TBG. CIRCULATED CMT UP THE 5 1/2" & THE 8 5/8" X 5 1/2" ANNULUS. PULLED TBG & TOPPED OFF HOLE WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4047	4050		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed

*Richard M. Lacey*

(TECHNICIAN)

RECEIVED

AUG 12 2011

KCC DODGE CITY

RECEIVED  
AUG 23 2011

KCC WICHITA

Form CP-1/3