

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-00027-00-01  
Spot: NWNENWNE Sec/Twnshp/Rge: 12-25S-16W  
4992 feet from S Section Line, 1656 feet from E Section Line  
Lease Name: MILLER OWWO Well #: 1  
County: EDWARDS Total Vertical Depth: 4655 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1020		WITH 440 SX CMT
PROD	5.5	4650	2060	WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/12/2011 1:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4150'. PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 08/12/2011 2:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 4150' & PUMP 35 SX CMT WITH 150# HULLS MIXED IN. PUMPED PLUGS THROUGH TBG. 1ST PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4225	4231		MISS LIME KINDE
4204	4224		BASAL PENN SAN

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED 60/40 POZMIX 4% GEL BY BASIC

Plugged through: TBG

District: 01

RECEIVED  
AUG 12 2011  
KCC DODGE CITY

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
AUG 23 2011  
KCC WICHITA

Form CP-2/3