

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21073-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 7-26S-11W
3661 feet from S Section Line, 4934 feet from E Section Line
Lease Name: NEWELL Well #: 1
County: PRATT Total Vertical Depth: 4376 feet

Operator License No.: 31465
Op Name: LYONS & LYONS, INC.
Address: 1519 S. BALTIMORE
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	411		WITH 350 SX CMT
PROD	4.5	4372	710	WITH 210 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/08/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SPOT 30 SX CMT THROUGH TBG AT 3950'. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/08/2011 9:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SPOT 40 SX CMT WITH 150# HULLS THROUGH TBG AT 3950'. 1ST PLUG AT 640' WITH 10 SX GEL, 50 SX CMT W/3% CC & 150# HULLS. 2ND PLUG AT 440' WITH 50 SX CMT W/3% CC & 150# HULLS. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4138	4148		VIOLA
3990	3997		MISS CHERT


RECEIVED
AUG 23 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA CASING LEAK** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED

AUG 12 2011

KCC DODGE CITY

Form CP-13