

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Wallace County. Sec. 13 Twp. 15S Rge. 41W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NW NE


Lease Owner Wichita Industries, Inc.
Lease Name Bedker Well No. 1
Office Address 1700 Broadway, Denver, Colo. 80202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed 12-22 19 76
Application for plugging filed 12-22 19 76
Application for plugging approved 12-22 19 76
Plugging commenced 12-22 19 76
Plugging completed 12-22 19 76

Reason for abandonment of well or producing formation
 No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production
19 76

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5474
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surf.	334	8-5/8"	327	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Fluid to 1450', plug, 70 sx cement;
Fluid to 300', plug, 20 sx cement;
Fluid to 40', plug, 10 sx cement. DEC 29 1976
12-29-76

(If additional description is necessary use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of December, 19 76

My commission expires 8-25-80

Ella Priess
Ella Priess Notary Public.



DRILLERS' LOG

WICHITA INDUSTRIES, INC.
 No. 1 Bedker
 NE NW NE, Sec. 13-15S-41W
 Wallace County, Kansas

Surface Casing: 327' of
 8-5/8" cemented w/275 sx
 Class H cement, 3% cc.
 12-8-76

Commenced: 12-7-76
 Completed: 12-22-76

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 334
Shale	334 - 535
Shale & Shells	535 - 1948
Shale	1948 - 2345
Lime & Shale	2344 - 2767
Shale & Lime	2767 - 3334
Lime, shale & sand	3334 - 3545
Lime & Shale	3545 - 3705
Shale	3705 - 3829
Lime & Shale	3829 - 4265
Shale	4265 - 4403
Lime & Shale	4403 - 4950
Shale & Lime	4950 - 5071
Lime & Shale	5071 - 5190
Lime	5190 - 5297
Shale	5297 - 5357
Lime, Chert & Shale	5357 - 5407
Lime & Shale	5407 - 5474 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 27th day of December, 1976.

Ella Priess
 Ella Priess, Notary Public

