


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Wallace County, Sec. 16 Twp. 14 Rge. (E) 42 (W)
Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Trend Exploration Limited
Lease Name R. Waugh Well No. 1
Office Address 600 Capital Life Center, Denver, Colo. 80203
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 3, 19 69
Application for plugging filed (letter 12/9/69) Dec. 3, 19 69
Application for plugging approved Dec. 3, 19 69
Plugging commenced Dec. 3, 19 69
Plugging completed Dec. 3, 19 69
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	325'	8-5/8"	325'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 1825'. Set first plug @ 1825' w/100 sacks cement. Filled hole with heavy mud to 425'. Set second plug @ 425' w/40 sacks cement. Filled hole with heavy mud to 40'. Set third plug @ 40' w/10 sacks cement. Job complete @ 3:00 AM, 12/3/69. Cement pumped through drill pipe with Globe Cementing pump truck.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place - Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 Sutton Place, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of December, 19 69

Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

R. WAUGH #1
C NE SW Section 16-14S-42W
Wallace County, Kansas

Commenced: November 11, 1969
Completed: December 3, 1969

OPERATOR - Trend Exploration Limited

DEPTH	FORMATION	REMARKS
From	To	
0	265	Surface clay, shale and sand
265	325	Shale Ran 9 joints 8-5/8" casing, set @ 325' w/300 sacks cement.
325	1944	Shale and sand
1944	2425	Shale and shells
2425	2790	Shale and red bed
2790	2819	Anhydrite
2819	2890	Red bed
2890	3145	Shale
3145	3270	Shale, red bed and sandy lime
3270	3560	Shale and lime
3560	3640	Shale, red bed and lime
3640	3974	Shale and lime
3974	4037	Lime
4037	4220	Shale and lime
4220	4723	Lime
4723	4793	Lime and chert
4793	5073	Lime and shale
5073	5197	Lime
5197	5315	Lime and chert
5315	5413	Lime
5413	5580	Lime and chert
5580	5600	Arbuckle lime
5600	TD	Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1969
CONSERVATION DIVISION
Wichita, Kansas
12-10-1968

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SW Section 16-14S-42W, Wallace County, Kansas, to the best of my knowledge and belief.

E. E. Hall

B. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 9 day of December, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

