

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-199-20,190-0000

LEASE NAME Schemm 44-32

WELL NUMBER 1

330 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 32 TWP. 14S RGE. 42 (X) (W)

COUNTY Wallace

Date Well Completed D&A

Plugging Commenced 08-02-90

Plugging Completed 08-07-90

LEASE OPERATOR Union Pacific Resources Company

ADDRESS P.O. Box 7-MS 3407, Fort Worth, TX 76101-0007

PHONE# (817) 877-7325 OPERATORS LICENSE NO. 6417

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 08-03-90 (date)

by Don Butcher (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Morrow sd Depth to Top 4996' Bottom 5080'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From    | To   | Size   | Put In | Pulled out |
|-----------|---------|---------|------|--------|--------|------------|
| Morrow    | Oil     | Surface | 5253 | 5 1/2" | 5251'  | 2753'      |
|           |         |         |      |        |        |            |
|           |         |         |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

SEE OTHER SIDE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. \_\_\_\_\_

Address P.O. Box 1598, Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Union Pacific Resources Company

STATE OF Texas COUNTY OF Tarrant, ss.

Kris Curran (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Kris Curran

(Address) P.O. Box 7 - MS 3407

Fort Worth, Texas 76101-0007

Subscribed and sworn to before me this 20<sup>th</sup> day of August, 1990  
Carolyn J. Ballard  
Notary Public

My Commission Expires: 6/25/94



Set CIBP @ 5000'

RIH with dump bailer & dump 5 sx MIC cmt on plug.

Cut csg @ 2751'

With Halliburton 65-35 with 8% gel & 1/4# Flocele - 25 sx balanced plug  
2800-2648' followed by mud spacer across Stone Corral.

100 sx balanced plug 1850-1360' followed by mud spacer across Dakota

40 sx balanced plug 640-450' followed by mud spacer across surface csg shoe.

20 sx plug 100' to surface.