

15-199-20006-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Wallace County, Sec. 32 Twp. 14S Rge. 12W (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Ute Production Company

Lease Name Neena Development #32-47 Well No.

Office Address P. O. Box 1743, Grand Junction, Colorado 81501

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 16, 1972 19

Application for plugging filed May 15, 1972 19

Application for plugging approved May 15, 1972 19

Plugging commenced 4:00 PM May 16, 1972 19

Plugging completed 6:00 PM May 16, 1972 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 5280' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	1971	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole full of heavy mud,
110' cubic feet of cement to 1800'
through open end of drill pipe, solid
bridge at 40' with 1/2 sack hulls,
Halliburton plug, 10 cubic feet of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company

Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1972

Bernard Laudermilk, Notary Public.

My commission expires
BERNARD LAUDERMILK—NOTARY PUBLIC
My Commission Expires Jan. 22, 1974

15-199-20006-00-00

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- NEENA DEVELOPMENT

#32-42

Located: C NE NE, Section 32-14S-42W, Wallace County,
Kansas

OWNER: Ute Production Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 20, 1972
COMPLETED: May 16, 1972

TOTAL DEPTH: 5280'

<u>LOG</u>	
0 - 40	Casing
40 - 520	Sand and Shale
520 - 1020	Shale
1020 - 1758	Shale - Sand
1758 - 1950	Lime and Shale
1950 - 2097	Sand, Shale and Lime
2097 - 2251	Shale
2251 - 2820	Shale and Lime
2820 - 2940	Lime
2940 - 4060	Lime and Shale
4060 - 4170	Lime
4170 - 4228	Shale and Lime
4228 - 4694	Lime
4694 - 4770	Lime and Shale
4770 - 4790	Shale
4790 - 5152	Lime and Shale
5152 - 5280	Lime

CASING RECORD

Ran 494' 10 3/4" 30# surface pipe,
cemented with 160 sacks light-weight
with 2% cc, 100 sacks common with 3%
cc.

Flugged.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1972
CONSERVATION DIVISION
Wichita, Kansas