

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER. 15-199-20,095 -00-00

LEASE NAME Robben

WELL NUMBER 1-8A

2190 Ft. from S Section Line

2100 Ft. from E Section Line

SEC. 8 TWP. 14 RGE. 40 XXXXX(W)

COUNTY Wallace

Date Well Completed 11-12-86

Plugging Commenced 11-12-86

Plugging Completed 11-12-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Arrowhead Petroleum, Inc.

ADDRESS Box 8287, Wichita, KS 67220

PHONE#(316) 681-3921 OPERATORS LICENSE NO. 5533

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6, Carl Goodrow, State plugger

Is ACO-1 filed? no If not, is well log attached? no, Sent to operator for completion

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13-3/8	501	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pump heavy mud to 2750'; 1st plug at 2750' to 2650'-25 sacks; 2nd plug at 1700' to 1275'-100 sacks + 1 sack hulls; 3rd plug at 550' to 390'-40 sacks; 4th plug at 40', solid bridge to surface-25 sacks; 15 sacks in rathole; 10 sacks in mousehole. All cement 60/40 posmix, 6% gel, 3% ca.cl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Sec/Treas

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton


(Address) Jack K. Wharton, Sec./Treas
801 Union Center, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1986

Clarice M. Mize Notary Public

Commission Expires: 11-28-88

11-17-86
Form CP-4
Revised 07-86



Roberts and Koch

1540 Independence Plaza
400 W. Illinois
MIDLAND, TEXAS 79701
915-683-6231
Fax 915-683-6529

ROSS D. ROBERTS
CHARLES E. KOCH

May 29, 1998

Mr. David Williams
State Corporation Commission
Wichita State Office Building
Wichita, Kansas 67202

Dear David:

Last March I talked with you about searching for logs on two wells in Wallace County, Kansas. The wells are:

Arrowhead Pet. #1-8A Robben
WELLSITE GEOLOGIST:
TODD SEYMOUR

Sec. 8, T14S, R40W
API #20095
TD 5200' D&A 11-12-86

WESTERN ATLAS LOGGING
(316)-793-7821
GREAT BEND, KS.

**WELLSITE
GEOLOGIST:
CASEY GALLOWAY
773-5588**

Galloway Pet. Expl. 1-15
Schmalzried
(This well has restivity log
from 2650' to 2800' and
3800' to 4016')

Sec. 15, T14S, R39W
API #20168
TD 5355' D&A 2-11-89

RECEIVED
CORP COMM
-2 D 1:27

I have checked all Kansas State sources and numerous log libraries. I am still very much interested in getting logs on these wells and any leads or ideas would be helpful.

Please contract either myself or Ross Roberts at (915) 683-6231.

Sincerely,

ROBERTS AND KOCH



Bill Morgan, Jr.