

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-199-20,094-00-06

LEASE NAME Robben

WELL NUMBER 1-8

2250 Ft. from S Section Line

2100 Ft. from E Section Line

SEC. 8 TWP. 14S RGE. 40 ~~XX~~ or (W)

COUNTY Wallace

Date Well Completed 11-1-86

Plugging Commenced 11-1-86

Plugging Completed 11-1-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Arrowhead Petroleum, Inc.

ADDRESS P.O. Box 8287 Wichita, KS 67220

PHONE# (316) 681-3921 OPERATORS LICENSE NO. 5533

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6 State plugger Marion Schmidt

Is ACO-1 filed? no if not, is well log attached? no

Sent to operator for completion.

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	370'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Cemented with 100 sacks and 2 sacks celoflake from 1340' to 940'; 2nd plug with 100 sacks and 1 sack celoflake from 440' to 40'; 3rd plug 10 sacks at 40'. Solid bridge to surface. 15 sacks in rathole, 10 sacks in mousehole; all cement 60/40 posmix, 6% gel, 3% ca. cl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack L. Partridge

(Address) 801 Union Center, Wichita, KS 67202

Subscribed and sworn to before me this 5th day of November, 19 86

Clarice M. Mize Notary Public

My Commission Expires: November 28, 1988



NOV 6 1986
Rec'd
11-06-86