



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 17 1962
 9-17-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 11 September, 1962, authorized

The following plugging operation:

Operator's full Name: The Shallow Water Refining Company

Complete Address: 542 Petroleum Building, Wichita, Kansas

Lease Name: Hamilton Well No. # 1

Location: C NE/4 Sec. 9 Twp. 20 Rge. 33 (E)(W)

County Scott Total Depth: 2700'

Oil Well Gas Well X Input Well SWD Well

D & A Other well as hereafter indicated:

Operator was instructed to plug well as follows:

8 8/8" 222' Cemented w/175 sax. 4 1/2" Cemented w/125 sax. (2699' 4 1/2")

Plug bottom w/5 sax. cement. Heavy mud top of cement to 200'

Plug and 35 sax. cement at 200'

Heavy mud top of cement to 45'

Plug and 15 sax. cement 45' to Surface.

Very truly yours,

