



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 12 1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. George Lamb of Kewanee Oil Company has this

date requested permission to plug the following described well:

Mr. Lamb guarantees payment of the plugging fee.

Operator's full Name: Kewanee Oil Company,

Complete Address: Box # 360, Hoisington, Kansas.

Lease Name: Wasinger Well No. A-1

Location: NW-NW Sec. 12 Twp. 20 Rge. (E) (W) 33

County Scott Total Depth 4733 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lamb was instructed to plug the well as follows:

372'--8 5/8" Surface pipe, cement circulated with 270 Sx.  
4682'--5 1/2" Cemented with 100 Sx. Plugged back to 4657',  
Top of perforations @ 4608'.

Sand well back to 4595' and set 5 Sx cement with Dump Bailer.  
Pull 5 1/2" to 600' and circulate heavy gel mud & displace 20 Sx  
cement thru 5 1/2" .. Pull casing to 360' and displace 20 Sx cement  
thru 5 1/2". Pull 5 1/2" to 30' and fill hole with cement to bottom  
of cellar.

Very truly yours,

N. L. Nichols  
 Conservation Division Agent