



15-171-00049-0001

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 - 69
1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Sargent of Sargent's Csg. Pulling Ser., has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: 1107 No. Kansas Ave., Liberal, Kansas.

Lease Name: Rothfelder Well No. 1

Location: CSW-SW Sec. 7 Twp. 20 Rge. (E)(W) 33

County: Scott Total Depth 4870' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

376'--8 5/8" Surface casing, cement circulated with 200 Sx.
4870'--5 1/2" casing cemented on bottom with 225 Sx. Production packer stuck
@ 4056', parted tubing @ 3114'. Perforations open @ 4044' to 4054'.

Squeeze bottom of hole with 25 sacks cement, let set overnight, pull cas-
ing and squeeze hole with 5 sacks hulls, 20 sacks gel and 160 Sx. cement,
staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent