

State of Kansas



15-171-30067-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 8 1967  
5-8-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Sargent of Sargent's Casing Pulling has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: P.O. Box #6, Liberal, Kansas.

Lease Name: Pfeffinger Well No. A-1

Location: CSW-SW Sec. 29 Twp. 20 Rge. (E)(W) 34

County Scott Total Depth 4663 Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Sargent was instructed to plug the well as follows:

452'--8 5/8" Surface pipe, cement circulated with 275 Sx.  
4660'--4 1/2" Production casing cemented with 175 Sx. Top of cement @ 3800' (Temp. Survey). Well plugged back to 4619'. Top perforations from 4558' to 4610'.  
Squeeze bottom with 15 Sx. cement and 1/2 sack hulls, stop plug @ 4200'.  
Pull 4 1/2" casing to 750' and circulate heavy gel mud, pull 4 1/2" to 690' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 450' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" set bridge @ 30' and 5 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols  
Conservation Division Agent