



15-171-20021-0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 26 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Estel Fox of Morrison Producing Company, has this date requested permission to plug the following described well:

Mr. Fox guarantees payment of the plugging fee.

Operator's full Name: Morrison Producing Company,

Complete Address: 400 North Main, Eldorado, Kansas.

Lease Name: Deyer *BOYER* Well No. 1

Location: CSW-NE Sec. 17 Twp. 20 Rge. (E)(W) 34

County: Scott Total Depth 5017 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fox was instructed to plug the well as follows:

349'--8 5/8" Surface casing, cement circulated with 325 Sx.
Top of Dakota section @ 650'

Circulate hole with heavy mud. Pull DP to 850' and displace 100 Sx.
cement thru DP. Pull DP to 370' and displace 20 Sx. cement thru DP. Pull DP,
set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Finkel
 Conservation Division Agent