

State of Kansas



15:17:20002:0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION COMMISSION
JUL 31 1967
7-31-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cal Roberts of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Incorporated,

Complete Address: Box # 486, Great Bend, Kansas.

Lease Name: Easton Well No. 1

Location: CSW-NE Sec. 20 Twp. 20 Rge. (E)(W) 34

County Scott Total Depth 5150 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

445'--8 5/8" Surface pipe, cement circulated with 350 Sx. Dakota section from 1800' to 1965'.

Circulate hole with heavy mud, set plug thru DP from 2000' to 1700' with 100 Sx. cement. Pull DP to 430' and set plug from 430' to 370' thru DP with 20 Sx. cement. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent