



15-171-00074-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1965
5-26-65
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Clarence Seeber of Glen Elden Oil Co., has this date requested permission to plug the following described well:

Mr. Seeber guarantees payment of the plugging fee.

Operator's full Name: Glen Elden D&I Company,

Complete Address: Box # 464, Eldorado, Kansas.

Lease Name: Seeber Well No. 1-fee

Location: CSE 1/4 Sec. 31 Twp. 20 Rge. (E) (W) 32

County Scott Total Depth 2700 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Seeber was instructed to plug the well as follows:

325' -- 7" OD Surface pipe, cement circulated.
2700' 4 1/2" Production casing cemented with 150 Sx. Plug set above all perforations. 6 1/2" hole below surface. Shot Dakota sands @ 700' to check water. Wishes to save upper water zone between 250' and 300' for irrigation well.

Set plugging bridge at top of shot on 4 1/2" and 25 Sx. cement thru 4 1/2". Pull 4 1/2" to 400' and displace 25 Sx. cement thru 4 1/2". Pull 4 1/2" to 300' and wash out any excess cement with water.
Very truly yours,

K. L. Nichols
Conservation Division Agent