



GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 13 1960  
 1-13-60  
 CONSERVATION DIVISION  
 Wichita, Kansas

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date Jan 2, 1960, authorized the following plugging operation:

Operator's Full Name: James Ely  
 Complete Address: c/o Charles Drew Box 404 Garden City, Kansas  
 Lease Name: Ely Well No. 1  
 Location: NE NE NE Sec. 11 Twp. 20 Rge. 32 (E) (W)  
 County: Scott Total Depth: 5188  
 Oil Well  Gas Well  Input Well  SWD Well  D & A   
 Other well as hereafter indicated: \_\_\_\_\_

Operator was instructed to plug well as follows:

~~Gun Pitts circulate hole with heavy mud, set cementing plug at 600 ft  
 and displace 20 sack cement thru drill pipe, heavy mud to 240 ft  
 set cementing plug, and displace 20 sack cement, heavy mud to 30 ft.  
 set and tie cementing plug in place dump 1 sack hulls and 10 sack cement  
 cementing to base of cellar.~~

Very truly yours,

Gilbert P. Leiker  
 Signed: Gilbert P. Leiker  
 Conservation Division Agent