

15-077-30166-0000

FORM - CP-2
Rev. 9-8-64

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1966
10-14-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Webb Hill of Mack Oil Company has this date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas

Lease Name: Hoath Well No. # 1

Location: C SW SW Sec. 6 Twp. 33 Rge. 9 (E)(W) W

County Harper Total Depth 4781' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

262' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fill Hole with drilling mud to 240', bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat and mouse holes with 5 sacks.

Very truly yours,

Audie Elving
Conservation Division Agent