

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

Operator: License # 3581

Name: Red Oak Energy, Inc.

Address P.O. Box 783140

Wichita, KS 67278-3140

City/State/Zip 09-3099

Purchaser: _____

Operator Contact Person: Kevin C. Davis

Phone (316) 652-7373

Contractor: Name: Murfin Drilling Co.

License: 30606

Wellsite Geologist: Scott Banks

Designate Type of Completion

New Well Re-Entry Workover

Oil SWD S10W Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-Entry: old well info as follows:

Operator: _____

Well Name: _____

Comp. Date _____ Old Total Depth _____

Deepening Re-perf. Conv. to Inj/SWD
 Plug Back PBD
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Inj?) Docket No. _____

6/16/96 6/25/96 6/26/96

Spud Date Date Reached TD Completion Date

API NO. 15- 199-202380000

County Wallace plugged 6/26/96

S/2 NW - SE Sec. 7 Twp. 15 Rge. 41 X ^E/_W

1650 Feet from S (circle one) Line of Section

2026 Feet from E (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
NE, SE, NW or SW (circle one)

Lease Name Yoder Well # 1-7

Field Name Wildcat

Producing Formation D & A

Elevation: Ground 3812 KB 3817

Total Depth 5200 PBD _____

Amount of Surface Pipe Set and Cemented at 582 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan PHA, 10-2-98 U.C.
(Data must be collected from the Reserve Pit)

Chloride content N/A ppm Fluid volume 600 bbls

Dewatering method used evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name _____

Lease Name _____ License No. _____

Quarter Sec. Twp. S Rng. E/W

County _____ Docket No. _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Kevin C. Davis

Title President Date 9/28/98

Subscribed and sworn to before me this 28th day of September, 1998.

Notary Public Victoria Davis

VICTORIA DAVIS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10/21/2001

K.C.C. OFFICE USE ONLY
F Letter of Confidentiality Attached
C Wireline Log Received
C Geologist Report Received
Distribution
 XCC SUD/Rep NGPA
 KGS Plug Other
(Specify)

Operator Name Ped Oak Energy, Inc. Lease Name Yoder Well # 1-7
 Sec. 7 Twp. 15 Rge. 41 East West
 County Wallace

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken (Attach Additional Sheets.)	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	BASE ANHY	2803	+1019
Electric Log Run (Submit Copy.)	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	CHEROKEE	4762	- 940
List All E.Logs Run:	DIL, CND	MORROW SHALE	5014	-1192
		MORROW LIME	5094	-1274

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8"	24#	583	lite cement	240	3% cc 1/2#
				1" @ 90'	common	75	Flo
					common	100	

ADDITIONAL CEMENTING/SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No

Date of First, Resumed Production, SWD or Inj.	Producing Method
<u>D&A</u>	<input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)

Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
	<u>N-A</u>				

Disposition of Gas: Vented Sold Used on Lease (If vented, submit ACO-18.)

METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval: _____

ALLIED CEMENTING CO., INC.

0335

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

ORIGINAL

15-199-20238-0000
SERVICE POINT:

Oakley

DATE <u>6-18-96</u>	SEC <u>7</u>	TWP. <u>15^s</u>	RANGE <u>41^w</u>	CALLED OUT	ON LOCATION <u>6:30 PM</u>	JOB START <u>9:30 PM</u>	JOB FINISH <u>Midnite</u>
LEASE <u>Yoder</u>	WELL # <u>1-2</u>	LOCATION <u>Weskan 3E-8S-14W</u>	COUNTY <u>Wallace</u>	STATE <u>Kan</u>			

OLD OR NEW (Circle one)

CONTRACTOR <u>MurFin Dcys Co #14</u>	OWNER <u>Same</u>
TYPE OF JOB <u>Surface</u>	CEMENT
HOLE SIZE <u>12 1/4</u>	T.D. <u>583'</u>
CASING SIZE <u>8 5/8</u>	DEPTH <u>583'</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG. <u>43.88'</u>	
PERFS.	

AMOUNT ORDERED	<u>200 - SKs com, 3%CC 1/4"</u>	
	<u>240 SKs Lite, 3%CC, 1/2" Flo-Seal</u>	
COMMON	<u>200 SKs @ 7.20</u>	<u>1,440.00</u>
POZMIX	@	
GEL	@	
CHLORIDE	<u>15 SKs @ 28.00</u>	<u>420.00</u>
	<u>Lite - 240 SKs @ 6.65</u>	<u>1,596.00</u>
	<u>Flo-Seal 170# @ 1.15</u>	<u>195.00</u>
	@	
	@	
HANDLING	<u>440 SKs @ 1.05</u>	<u>462.00</u>
MILEAGE	<u>44 per sk/mile</u>	<u>1,320.00</u>
		TOTAL <u>5,433.00</u>

EQUIPMENT

PUMP TRUCK	CEMENTER <u>Walt</u>
# <u>300</u>	HELPER <u>Wayne</u>
BULK TRUCK	
# <u>212</u>	DRIVER <u>Jeff</u>
BULK TRUCK	
# <u>305</u>	DRIVER <u>Dean</u>

REMARKS:

SERVICE

mixed 240 SKs Lite Tailin w/
75 SKs com, 3%CC, Lost Partial
returns, Displaced Plug to insert
Lost Returns, ran 1" down to 90'
mixed 100 SKs cement, Fluid Fell
down hole, waited 30 minutes,
mixed 25 SKs com, Fluid 6" down
til 40'

DEPTH OF JOB	<u>583'</u>	
PUMP TRUCK CHARGE		<u>445.00</u>
EXTRA FOOTAGE	<u>283'</u> @ <u>4.16</u>	<u>116.03</u>
MILEAGE	<u>75-miles @ 2.85</u>	<u>213.75</u>
PLUG	<u>8 5/8 Surface @</u>	<u>45.00</u>
	@	
	@	
		TOTAL <u>819.78</u>

CHARGE TO: Red Oak
STREET 200 W Douglas #510
CITY Wichita STATE Kansas ZIP 67

FLOAT EQUIPMENT

1 - Baffle Plate	@	<u>135.00</u>
1 - Centralizer	@	<u>61.00</u>
2 - Baskets	@ <u>200.00</u>	<u>400.00</u>
	@	
	@	
		TOTAL <u>596.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
TOTAL CHARGE _____
DISCOUNT _____

SIGNATURE Matthew Finney

IF PAID IN 30 DAYS
ALLIED CEMENTING CO., INC.
P.O. BOX 31
RUSSELL, KANSAS 67665

ALLIED CEMENTING CO., INC. 5992

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

ORIGINAL

15-199-20238-00-00

SERVICE POINT:

Neosho City

DATE <u>6-26-96</u>	SEC. <u>7</u>	TWP. <u>15</u>	RANGE <u>41</u>	CALLED OUT <u>3:00 AM</u>	ON LOCATION <u>7:00 AM</u>	JOB START <u>11:00 AM</u>	JOB FINISH <u>2:45 PM</u>
LEASE <u>Under</u>	WELL # <u>1-7</u>	LOCATION <u>Jubilee 16N-9W-4N</u>			COUNTY <u>Wallace</u>	STATE <u>KS</u>	

CONTRACTOR <u>Muskin</u>	OWNER <u>Same</u>
TYPE OF JOB <u>R Plug</u>	CEMENT
HOLE SIZE <u>7 7/8</u>	T.D. <u>5200'</u>
CASING SIZE	DEPTH
TUBING SIZE	DEPTH
DRILL PIPE <u>4 1/2"</u>	DEPTH <u>2780</u>
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	

AMOUNT ORDERED <u>200 60/40 6% 0 1/4" F10</u>
COMMON <u>120</u> @ <u>7.20</u> <u>864.00</u>
POZMIX <u>80</u> @ <u>3.15</u> <u>252.00</u>
GEL <u>10</u> @ <u>9.50</u> <u>95.00</u>
CHLORIDE @
<u>Flo Seal 50</u> @ <u>1.15</u> <u>57.50</u>
HANDLING <u>200</u> @ <u>1.05</u> <u>210.00</u>
MILEAGE <u>72</u> <u>576.00</u>
TOTAL <u>\$2054.50</u>

EQUIPMENT

PUMP TRUCK CEMENTER <u>Mike</u>
<u>224</u> HELPER <u>Bob</u>
BULK TRUCK DRIVER <u>Bill</u>
<u>116</u> DRIVER

REMARKS:

<u>1st Plug at 2780' w/ 25 Ska</u>
<u>2nd Plug at 1700' w/ 100 Ska</u>
<u>3rd Plug at 630' w/ 40 Ska</u>
<u>4th Plug at 40' w/ 10 Ska</u>
<u>Pat Hole - 15 Ska - New Hole 10 Ska</u>

SERVICE

DEPTH OF JOB	
PUMP TRUCK CHARGE	<u>445.00</u>
EXTRA FOOTAGE @	
MILEAGE <u>72</u> @ <u>2.85</u>	<u>205.20</u>
PLUG <u>1-8 1/2" Hole</u> @ <u>23.00</u>	<u>23.00</u>
<u>Dry</u> @	
TOTAL <u>\$673.20</u>	

CHARGE TO: Red Oak Energy Inc.
STREET 200 W. Douglas Suite 510
CITY Wichita STATE Ks ZIP 67202

FLOAT EQUIPMENT

@	
@	
@	
@	
@	
TOTAL	

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX <u>-0-</u>
TOTAL CHARGE <u>\$2727.70</u>
DISCOUNT <u>\$409.16</u> IF PAID IN 30 DAYS

Net \$2318.54

SIGNATURE [Signature]