


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

15-051-20252-0880
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ellis County. Sec. 2 Twp. 13 Rge. 16 (E) W (W)
Location as "NE/CNW/SE" or footage from lines SW NW SE
Lease Owner Dreiling Oil, Inc.
Lease Name H. B. Mabee Windholz Well No. 1
Office Address Rt. #2, Victoria, Kansas 67671
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 5-16 19 68
Application for plugging filed 7-16 19 73
Application for plugging approved 7-17 19 73
Plugging commenced 10-15 19 73
Plugging completed 10-15 19 73
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 4-73 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Box 582, Hays, KS 67601
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,460 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	146'	
Casing				4 1/2"	3,450'	2,070'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 25 sacks gel, 25 sacks Hulls, 130 sacks 50/50 Poz Mix, 50% Gel
Maximum Pressure 300#, Shut in Pressure 150#.

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1975

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Russ Casing Pulling, Inc.
Address Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Joe Hess, Sec. Treas. of Drig. Contr. (~~conservation agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Joe Hess, Rt. #2, Victoria, KS 67671
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of October, 19 73



Cecilia Basgall
Cecilia Basgall
Notary Public.

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

15-051-20252-0000

WELL LOG

Company	H. B. Mabee Box 94718 Oklahoma City, Oklahoma 73109	Sec. 2	Twp. 13	Rng. 16
Farm	Windhols No. 1	Location	SW NW SE	
Total Depth	3460'	County	Ellis	
Comm.	3-4-68 Comp. 3-16-68	Elevation:	1987'	K.B.
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		1984'	D. F.
			1982'	G. R.

Casing Record
146' - 8 3/8"
3450' - 4 1/2"

Cement Record
110 sacks cement
30 sacks 50/50 pes, 4X gal with 12 1/2# gilsonite
200 sacks 60/40 pes 2X gal, 18X salt

Production:

Figures Indicate Bottom of Formations		
0'	110'	Sand & Clay
110'	143'	Blue Shale
143'	340'	Shale
340'	420'	Sand & Shale
420'	640'	Shale & Shells
640'	1107'	Shale & Shells
1107'	1150'	Anhy.
1150'	1190'	Shale & Shells
1190'	1700'	Shale & Shells
1700'	3065'	Line & Shale
3065'	3145'	Line & Shale
3145'	3460'	Line
3460'	T.B.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Windhols #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 17th day of May 1968.

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970



RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1973
CONSERVATION DIVISION
Wichita, Kansas