

KCC OIL/GAS REGULATORY OFFICE

DATE February 4, 5 & 6, 1998
OPERATOR Viking Resources, Inc. # 5011
NAME 105 S. Broadway, Ste. 1040
& ADDRESS Wichita, KS 67202
PHONE NO. 316-262-2502
OPER. OTHER

[] New Situation
[x] Response to Request
[] Follow-up
200' NE of LOCATION NW SW NE, SEC 32, T 16 S, R 31 W
LEASE Harper Well # 2
COUNTY Scott API#15-171-20,526

REASON FOR INVESTIGATION: Alternate II cement completion

LEASE INSPECTION

PROBLEM:

PERSON(S) CONTACTED:

FINDINGS: 8 5/8" at 259', TD 4048', Port collar at 2330'

2/4/98 Allied cemented w/450 sx 60/40 Pozmix 8% gel 1/4# flowseal. Well didn't circulate.

COMPLAINT

2/5/98 L & K Wireline ran temperature survey. Cement at 975'. L & K perforated at 900-902'. Couldn't get cement. Shut down.

2/6/98 Ran tubing and packer in hole. Allied Cementing pumped 7 sx gel, well circulating. Pumped 200 sx 60/40 Pozmix 6% gel and 75 sx common 3% cc. Put approx. 75 sx cement into pit. Maximum pressure 500 psi. Squeezed perms.

ACTION/RECOMMENDATIONS: photos taken: Alternate II cementing requirements completed.

FEB 13 1998
2-13-98

FIELD REPORT X

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Kevin Strube

2/6/98