

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHALLOW WATER REFINING COMPANY
Farm- Petro No. 1


SEC. 3 T. 20 R. 35W
C SE NW

Total Depth. 4745'
Comm. 5-27-61
Shot or Treated.
Contractor. Capitt Drig.
Issued. 3-3-62

Comp. 6-16-61

County Scott KANSAS

K.G.S. LIBRARY



CASING:

8 5/8" 376' cem w/300 sx.
4 1/2" 2688' cem w/100 sx.

Elevation. 2969' RB

Production. 6,000,000 CFG

Figures Indicate Bottom of Formations.

clay	80
sand	150
shale	350
sand & shale	1240
shale & shells	1400
lime & shale	1649
shale & sand	1837
shale & red bed	1875
shale & lime	2050
lime & shale	2406
shale & lime	2560
lime & shale	2642
shale & lime	3025
lime & shale	3167
lime	3237
lime & shale	3334
lime	3538
lime & shale	3775
lime chalky	3890
lime	4015
lime	4235
lime & shale	4290
shale & lime	4360
lime	4574
Core #1	4588
Core #2	4599
Core #3	4648
Core #4	4697
lime	4745 RTD
Total Depth	

Read 3-3-62

TOPS: SCOUT	
Anhydrite	2003
Base Stone Corral	2180
Wellington	2422
Hollenberg	2597
Herington	2622
Kridar	2639
Winfield	2672
Ft. Riley	2733
Heebner	3380
Lansing	3850
Marmaton	4273
Cherokee	4454
Morrow	4604
Mississippi	4660

Perf: 4 shots/ft. 2642-48'
" " 2625-36'