

**KANSAS CORPORATION
COMMISSION**

130 S. Market
Rm 2078
Wichita, KS 67226
Fax 316-337-6211

District #1 210 E Frontview Ste A Dodge City KS 67801 620-225-8888 FAX 620-225-8885
 District #2 3450 N Rock Road Bldg 600 Ste 601 Wichita KS 67226 316-630-4000 FAX 316-630-4005
 District #3, 1500 W. 7th Chanute KS 66720 620-432-2300 FAX 620-432-2309
 District #4, 2301 E. 13th Hays KS 67501 785-225-0550 FAX 785-425-0564
Check Appropriate District Office

Emergency Plugging Request

Company Name: Trans Pacific Oil Corporation Request Date: August 23, 2011

Address: 100 S. Main, Suite 200 City/State/Zip: Wichita, KS 67202

Phone #: 316-262-3596 Fax # _____

Contact Person: Alan Banta title: President

Well Name: Vopat G 7-A API # 15-053-20164-00-00

Location: FSL _____ ; FEL _____ ' Qtr-Qtr-Qtr E/2 SW NW 1980'FNL & 990'FWL

Section 21 Township 14 Range 10W County: Ellsworth

Type of well: Oil Gas _____ SWD _____ (Docket # _____) Other _____

Casing Information: Surface Pipe 8 5/8" @ 259' Prod. Casing 4 1/2" @ 2912'

Top and Bottom Depth of Fresh and Useable Ground Water: _____ ' Formation name: _____

All II/squeezes in well: Operator was attempting to run a casing MIT for 10 year TA exception.

Junk in hole? Yes No _____ Description and attempts to remove: 2 jts of tubing and mud anchor left in the hole. Top of parted tubing @ 2779'. Attempts to retrieve junk have failed.

Perf from 2826-38, LKC

Reason for emergency plug request: Junk in hole, casing leak, fluid level @ 380' above the salt section. Depth to casing leak unknown. Salt top @ 950', Salt base @ 1150'.

Proposed plugging method: Spot 20 sx @ 2779', 35 sx @ 1200', 35sx @ 900', Circ from 310' to surface. All cement is to be common cement.

Name of Landowner: N/A

Has the KSONA-1 form been filed? Yes _____ No If NO when will form be sent to landowner: 8/24 OR 8/25

Expected Date to plug well: 8 / 24 / 2011

District Supervisor Approval for Emergency Plug.

TRANS PACIFIC OIL CORPORATION is hereby approved to plug the VOPAT G 7-A well on this day

8/24/2011

John K. [Signature] DISTRICT SUPERVISOR
authorized signature

The authority to plug this well does not supersede K.S.A. 55-151 but is in agreement with K.S.A. 55- _____ which states in part that the Conservation Division shall protect and prevent the waste of fresh and usable water and correlative rights. The approval to plug this well does not include an inquiry into well ownership or the requesting operator's legal right to plug the well. This approval in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.