

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-071-20712-0000

API NUMBER 15-20712-0000

LEASE NAME Kriss

WELL NUMBER 3-26

330 Ft. from S Section Line

1130 Ft. from E Section Line

SEC. 26 TWP. 16 RGE. 42 (E) or (W)

COUNTY Greeley

Date Well Completed 10/22/99

Plugging Commenced 10/24/99

Plugging Completed 10/25/99

MAR - 3 2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CONSERVATION DIVISION
Wichita, Kansas

LEASE OPERATOR Red Oak Energy, Inc.

ADDRESS 7701 E. Kelllogg, Suite 710, Wichita KS 67207

PHONE# (316) 652-7373 OPERATORS LICENSE NO. 03581

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Durrant and Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation D & A Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface		8 5/8"	378'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 2600 feet to MH feet each set.
See attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Red Oak Energy, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Kevin C. Davis

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Signature]

(Address) 7701 E. Kelllogg, #710, Wichita KS

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 2000

[Signature]
Notary Public

My Commission Expires: Oct. 21, 2001

15-071 -2071200-05

Attachment for CP-4 Kriss #3-26 Greeley County, KS Red Oak Energy Inc

Trip in hole open ended to 2600' to plug. Spot 50 sx 60/40 Pozmix, 3% Gel, 2% cc, 1/4# Floccelle. 1880' - 80 sx @ 12:45 p.m., 10/24/99. Wait 4 hrs, tried to fill hole and wouldn't. 1880' - 80 sx, 60/40 Pozmix @ 6:00 p.m., 10/24/99. Wait 4 hrs, tried to fill hole and wouldn't. Cement @ 1850' w/75 sx ASC @ 2:30 a.m., 10/25/99. Wait 4 hrs, tried to fill hole and wouldn't. Trip in hole to spot cement on bottom @ 2600' +/- . Hit bridge @ 2068'. Tried to fill hole and wouldn't mix up. Pump down pipe and hole filled, took 75 bbls +/- . Called KCC - Steve Durrant said to pull up to 1880' and re-cement w/50 sx ASC, 2% cc @ 12:30 p.m., 10/25/99. Pulled up to 1400' and waited 1 hr. Finished cementing w/ASC, 2% cc, 1200' w/50 sx, 390' w/50 sx, 40' w/10 sx, RH w/15 sx, MH w/10 sx. Job completed @ 5:00 p.m. 10/25/99. Kevin Strube, KCC, on location.

RECEIVED
STATE CORPORATION COMMISSION

MAR - 3 2000

CONSERVATION DIVISION
Wichita, Kansas