

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-071-20,679-00-00

LEASE NAME Kriss

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-26

2300 Ft. from S Section Line

330 Ft. from W Section Line

SEC. 26 TWP. 16S RGE. 42 (E) or (W)

COUNTY Greeley

Date Well Completed 11-02-97

Plugging Commenced 10-31-97

Plugging Completed 11-02-97

LEASE OPERATOR Red Oak Energy, Inc.

ADDRESS 200 W. Douglas, #510, Wichita, KS 67202

PHONE#(316) 265-9925 OPERATORS LICENSE NO. 03581

Character of Well D/A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-31-97 (date)

by Steve Pfelfer (KCC District Agent's Name).

Is ACO-1 filed? Enclosed If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Fill with heavy mud. 1st plug from 2725'-2525' with 50 sks. 2nd plug from 1900'-1580' with 80 sks; 3rd plug from 900'-700' with 50 sks, 4th plug from 380'-180' with 50 sks, 5th plug from 40'-0' with 10 sks, 15 sks in rat hole. Total of 255 sks*60/40 pos, 6% gel, 1/4# floeal per sk.

KANSAS CORPORATION COMMISSION

Name of Plugging Contractor Abercrombie RTD, Inc. DEC 16 1997 License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CONSERVATION DIVISION WICHITA, KS

STATE OF Kansas COUNTY OF Sedgwick, ss.

KEVIN C. DAVIS (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Kevin C. Davis

(Address) 200 W. Douglas, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 16th day of December, 19 97

Victoria Davis
 Notary Public

