

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20,431-00-00

LEASE NAME Young Cattle Co.

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4620 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 22 TWP. 16S RGE. 42 (S) or (W)

COUNTY Greeley

LEASE OPERATOR Boger Brothers Drilling, Inc.

ADDRESS P. O. Box 723, Great Bend, KS 67530

PHONE#(316) 792-8151 OPERATORS LICENSE NO. 9421

Date Well Completed 2/20/87

Character of Well D&A

Plugging Commenced 2/20/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/20/87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5220 RTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	8-5/8"	0	324	8-5/8"	324	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
Mud laden fluid 5220-2726'

50 sks cement @ 2726' 10 sks cement @ 40'

50 sks cement @ 1300' 10 sks cement in rathole

40 sks cement @ 350' 10 sks cement in mouse hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 87

[Signature]  
Notary Public

MAR 11 1987

My Commission Expires: July 29, 1989



15-071-20431-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Boger Brothers Drilling, Inc.  
P. O. Box 723  
Great Bend, KS 67530

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Young Cattle Co. WELL #1

LOCATION: W/2 NW NW  
Section 22-16S-42W  
Greeley County, Kansas

Log Total Depth: 5219'

ROTARY TOTAL DEPTH: 5220'

COMMENCED: 02/12/87

CASING: 8-5/8" @ 324' w/200 sks cement

ELEVATION: 3832' K.B.

COMPLETED: 02/20/87

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top soil & Sand	40'	Anhydrite	2726'
Sand & Shale	330'	Shale	2890'
Shale	2137'	Lime & Shale	4234'
Shale & Sand	2525'	Lime (R.T.D.)	5220'
Shale	2695'		


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
\_\_\_\_\_  
Kyle B. Branum

Subscribed and sworn to before me on March 10, 1987.

My commission expires: July 29, 1989.

  
\_\_\_\_\_  
Patricia L. Schawo, Notary Public



MAR 11 1987