

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20.437-00-00

LEASE NAME Young Cattle Co.

WELL NUMBER 2

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 22 TWP. 16 SRGE. 42 (E) or (W)

COUNTY Greeley

Date Well Completed 4/16/87

Plugging Commenced 4/16/87

Plugging Completed 4/16/87

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Boger Brothers Drilling Co.

ADDRESS Box 723, Great Bend, KS 67530

PHONE# (913) 792-8151 OPERATORS LICENSE NO. 9421

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? 6

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		-0-	300	8-5/8"	300	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Mud laden fluid 5200 - 2735'

50 sks cement @ 2735 10 sks cement @ 40'

80 sks cement @ 1670 15 sks cement in rat hole

50 sks cement @ 330 10 sks cement in mouse hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum

(Address) Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 21st day of April, 1987

My Commission Expires: July 29, 1989



APR 22 1987

RECEIVED  
STATE CORPORATION COMMISSION  
Form CP-4  
Revised 07-86  
Wichita, Kansas

15-071-20437-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Boger Brothers Drilling Co.  
P. O. Box 723  
Great Bend, KS 67530

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Young Cattle Co. WELL #2

LOCATION: NW NE NW  
Section 22-16S-42W  
Greeley County, Kansas

LOG TOTAL DEPTH: 5190'

ROTARY TOTAL DEPTH: 5200'

COMMENCED: 4/8/87

CASING: 8-5/8" @ 300' w/180 sks cement

ELEVATION: 3832' K.B.

COMPLETED: 4/16/87

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top soil & Sand	43'	Anhydrite	2731'
Sand & Shale	302'	Shale	3702'
Shale	1856'	Lime & Shale	4965'
Shale & Sand	2651'	Lime (R.T.D.)	5200'
Shale	2693'		


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Kyle B. Branum

Subscribed and sworn to before me on April 21, 1987.

My commission expires: July 29, 1989.

  
Patricia L. Schawo, Notary Public



RECEIVED  
STATE CORPORATION COMMISSION

APR 22 1987

CONSERVATION DIVISION  
Wichita, Kansas