


15-071-20117-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Greeley County. Sec. 27 Twp. 17 Rge. 39 X/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
C SW SW



Locate well correctly on above Section Plot

Lease Owner American Public Energy  
Lease Name Bauer Well No. 1  
Office Address 8350 N. Central Expressway, Dallas, Tex  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Gas  
Date Well completed 19  
Application for plugging filed 1-24 1977  
Application for plugging approved 1-24 1977  
Plugging commenced 1-24 1977  
Plugging completed 1-24 1977  
Reason for abandonment of well or producing formation  
Non Comercial value  
If a producing well is abandoned, date of last production  
None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Balthazor  
Producing formation Hugoton Depth to top 2854' Bottom 2864' Total Depth of Well 3040'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0'	264'	8 5/8"	264'	0'
Production		0'	3039'	4 1/2"	3039'	20'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 1 sack hulls & 10 sacks cement to 2700' pressured to 750 lbs.  
Displaced w/ mud to 1000'  
Spotted 10 sacks cement 1000' to 880'  
Displaced w/ mud to 300' FEB 1977  
Spotted 15 sacks cement 300' to 160' 02-14-77  
Displaced w/ mud to 40'  
Put bridge & 10 sacks cement 40' to 0'  
Cut off 8 5/8" 42" below ground level.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling  
Box F, Sublette, Kansas 67877 Kans Permit # 766

STATE OF KANSAS COUNTY OF Haskell, ss.  
I Edgar J. Eves (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

Edgar J. Eves  
Box F, Sublette, Kansas 67877  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 th day of January, 1977

Sandra L. Eves  
Notary Public.

My commission expires 12-8-80



DRILLERS' LOG

15-071-20117-00-00

AMERICAN PUBLIC ENERGY CO.  
No. 1 Bauer  
SW SW, Sec. 27-17S-39W  
Greeley County, Kansas

Commenced: 9-7-76  
Completed: 9-11-76

Surface Casing: 257' of  
8-5/8" cemented w/200 sx  
common cement, 38 cc. 9-7-76

FORMATION

DEPTH

Surface Hole	0 - 264
Shale	264 - 605
Shale, Shells & Sand	605 - 1620
Shale & Lime	1620 - 2445
Shale, Sand & Lime	2445 - 2835
Shale & Lime	2835 - 3040 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 16th day of Sept. 1976.

*Ella Priess*  
Ella Priess, Notary Public

