

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-071-20114-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Greeley County, Sec. 21 Twp. 17 Rge. 39 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
C SW SW


Lease Owner American Public Energy  
Lease Name Mai Well No. 1  
Office Address 8350 N Central Expressway Dallas, Texas  
Character of Well (Completed as Oil, Gas or Dry Hole)

Gas  
Date Well completed 19  
Application for plugging filed 1-24 1977  
Application for plugging approved 1-24 1977  
Plugging commenced 1-25 1977  
Plugging completed 1-25 1977

Reason for abandonment of well or producing formation  
Non Comercial Value  
If a producing well is abandoned, date of last production  
None 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Balthazor  
Producing formation Hugoton Depth to top 2860' Bottom 2870' Total Depth of Well 3030'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above  
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0'	262'	8 5/8"	262'	0'
Production		0'	3023'	4 1/2"	3023'	819'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Pumped 1 sack hulls & 10 sacks cement to 2715' Pressured to 750 lbs.  
Displaced w/ mud to 1100'  
Spotted 10 sacks cement 1100' to 980'  
Displaced w/ mud 980' to 260'  
Spotted 25 sacks cement 260' to 160'  
Displaced w/ mud 160' to 40'  
Put bridge & 10 sacks cement 40' to 0'  
Cut off 8 5/8" 42" below ground level.

02-14-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling  
Box F, Sublette, Kansas 67877 Kansas permit # 766

STATE OF KANSAS COUNTY OF Haskell, ss.  
I Edgar J. Eves (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves  
Box F, Sublette, Kansas 67877  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 th day of January, 1977

Londra L Eves  
Notary Public.

My commission expires 12-9-80



DRILLERS' LOG

AMERICAN PUBLIC ENERGY CO.

No. 1 Mai

C SW SW, Sec. 21-17S-39W

Greeley County, Kansas

Commenced: 8-5-76

Completed: 8-8-76

15-071-20114-00-00

Surface Casing: 255' of  
8-5/8" cemented w/175 sx  
common cement, 3% cc.  
8-5-76

FORMATION

DEPTH

Surface Hole	0	-	263
Sand & Shale	263	-	540
Shale & Sand Streaks	540	-	1560
Shale, Sand & Lime Strks	1560	-	1932
Shale	1932	-	2745
Lime & Shale	2745	-	3030 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

Very truly yours

D N B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 18th day of August 1976.

*Ella Priess*

Ella Priess, Notary Public

<i>Ella Priess</i>
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976

AND MATTERS HEREIN CONTAINED ARE TRUE AND CORRECT.

*James L. Donelson*