


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
MaRe Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-071-00008-00-00  
WELL PLUGGING RECORD

Greeley County. Sec. 8 Twp. 17-S Rge. (E) 39(W)

Location as "NE/CNW/SE" or footage from lines C SE SE  
Lease Owner Whitehall Oil Company, Inc.  
Lease Name Edwina P. Trigg Well No. 1  
Office Address 1814 Mercantile Bank Building, Dallas 1, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 21 19 58  
Application for plugging filed 6 March 19 59  
Application for plugging approved Verbal Approval - 11-21\* 19 58  
Plugging commenced November 21 19 58  
Plugging completed November 21 19 58  
Reason for abandonment of well or producing formation No production



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rivers  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5353 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	2630	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Filled hole with 9.8 lb mud. Placed 35 sacks cement at 600' to 520' and 15 sacks cement in top of surface casing 0' to 40'.

\* Verbal permission was given by Mr. M. A. Rivers

STATE CORPORATION COMMISSION  
MAR 9 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton Oil Well Cementing Company  
Address Elkhart, Kansas

STATE OF Texas, COUNTY OF Dallas, ss.  
James B. Neale (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James B. Neale  
1814 Mercantile Bank Bldg., Dallas, Texas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 59  
McQuinn X. Rivers  
Notary Public.

My commission expires June 1, 1959

PLUGGING  
FILE SEC 0 T. 17 R. 39W  
BOOK PAGE 1 LINE 11

COMMENCED 10-29-58  
COMPLETED 11-21-58

15-071-00008-00-00  
WHITEHALL OIL COMPANY  
EDWINA P. TRIGG #1  
GREELEY COUNTY, KANSAS

0 162 Clay  
162 198 Sand  
198 235 Sand, clay  
235 650 Shale and clay  
650 955 Shale, sand, clay  
955 1495 Anhydrite, shale  
1495 1505 Hard sandy lime  
1505 1609 Sand, anhydrite strks.  
1609 1678 Shale, anhydrite strks.  
1678 1807 Red Bed  
1807 1954 Shale, Red Bed, anhydrite  
1954 1960 Anhydrite  
1960 2312 Shale and salt  
2312 2372 Shale and anhydrite  
2372 2493 Lime  
2493 2612 Shale, sand, anhydrite  
2612 2640 Dolomite  
2640 2680 Lime  
2680 2855 Shale wi strks. anhydrite  
2855 2965 Shale  
2965 2988 Sand  
2988 3000 Shale  
3000 3075 Shale, sand  
3075 3162 Shale, lime strks.  
3162 3348 Shale, lime  
3348 3380 Lime  
3380 3441 Lime and shale  
3441 3627 Lime  
3627 3700 Dolomite and lime  
3700 3812 Lime  
3812 3884 Lime and shale  
3884 4017 Lime and sand strks.  
4017 4738 Lime  
4738 4807 Lime wi chert  
4807 4909 Lime  
4909 4952 Lime wi chert  
4952 4965 Lime and shale  
4965 5006 Shale  
5006 5120 Shale and lime  
5120 5358 Lime (Mississippian)  
T.D.

8-17-39W  
CSESE

RECORDED  
INDEXED  
MAR 9 1959  
CONSERVATION DIVISION  
Wichita, Kansas

Schlumberger 11-2-58  
8 5/8" @ 2640' wi 900 sacks 4% jell  
300 sacks 2% C.C.  
Plug down 1:30 A.M. 11-3-58  
Schlumberger 11-21-58 T.D. 5351'  
Plug of 35 sacks @ 650' and 15 sacks at top.  
D & A

I, Henry S. Grace, first being duly  
sworn on oath, state that I have full  
knowledge of the facts and matters  
herein and that same are true and correct.

Henry S. Grace  
H.S. Grace

Subscribed and sworn to before me this  
26th day of November, 1958.

Connie C. Bennett  
Connie C. Bennett Notary Public  
Wichita County, Texas.

PLUGGING  
FILE SEC 0 T 17 R 39W  
BOOK PAGE 1 LINE 11