

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1973
2-26-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Incorporated - Petroleum Resources,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Beckley Well No. 2

Location SE-NE-NE Sec. 13 Twp. 18 Rge. (E) (W) 32

County Scott Total Depth 4597'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dunne-Gardner Petroleum, Incorporated,

Address 200 West Douglas, Wichita, Kansas. License No.

Operation Completed: Hour 5:15 AM Day 24 Month 2 Year 1973

The above well was plugged as follows:

610'--8 5/8" Surface casing, cement circulated with 450 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225 to 900'. Pulled DP to 620' and displaced 30 Cu. Ft. cement thru DP
from 620' to 545'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dehals*
Well Plugging Supervisor

INDEXED
DATE 2/28/73
INV. NO. 7052-W