

15-185-01126-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
AUG 12 1963
8-12-63
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Wilson "W" Well No. # 1

Location C SW SW Sec. 18 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4480

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 12:30PM Day 8th Month August Year 1963

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cemented with 250 sacks. 4315' of 5 1/2" long
string, cemented with 150 sacks. Top perferation 4202'. Sanded to 4190',
cemented with 5 sacks. Hole has been flowing and a squeeze job will be
necessary. 10 sacks of mud and 75 sacks cement was pumped into the hole
through a swage, in the surface pipe, at a pressure of 250 lbs.
3275' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ardie Elving
Well Plugging Supervisor

DATE 8/12/63
INV. NO. 7559-W