

15-171-20038-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1972  
5-24-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc., & Petroleum Resources,  
Complete Address Box #18407, Wichita, Kansas. 67218  
Lease Name Beckley Well No. E-1  
Location NE-SW-SE Sec. 26 Twp. 18 Rge. (E) (W) 32  
County Scott Total Depth 4693'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Rains & Williamson Oil Company, Inc.,  
Address 475 Page Court, Wichita, Kansas. License No.       
Operation Completed: Hour 1: PM Day 21 Month 5 Year 1972

The above well was plugged as follows:

661'--8 5/8" Surface casing, cement circulated with 400 Sx.  
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement  
thru DP from 1275' to 950'. Pulled DP to 700' and displaced 30 Cu. Ft. cement thru  
DP from 700' to 625'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Diebel  
Well Plugging Supervisor

INVOICED  
DATE 5/25/72  
INV. NO. 5751-11