



Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Specter Pipe and Supply Company, Incorporated,

Complete Address Box #169, Russell, Kansas.

Lease Name Newby Well No. B-2

Location CNE-SW Sec. 23 Twp. 18 Rge. (E) (W) 32

County Scott Total Depth 4740'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Lynch Casing Pulling Company,

Address R. R. #4, Great Bend, Kansas. License No. 457

Operation Completed: Hour 5:00 PM Day 11 Month 8 Year 1969

The above well was plugged as follows:

306'--8 5/8" Surface casing, cement circulated with 275 Sx.  
4739'--5 1/2" Production casing cemented on bottom with 225 Sx. Top perforations from  
3961' to 3966'. No plug back shown.

Pushed plug to 3800', sanded to 3750' and set 5 Sx. cement with dump bailer. Pulled  
5 1/2" casing to 1250' and circulated heavy mud using 15 Sacks gel then displaced 100 Sx.  
cement then 5 1/2" using heavy gel mud to displace. Pulled 5 1/2" to 325' and displaced 25  
Sx. cement thru 5 1/2". Pulled 5 1/2", set rick bridge @ 30' and 10 Sx. cement to bottom  
of cellar. (Recovered 2006' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

DATE 8-18-69  
INV. NO. 323-W

Signed: M. L. Nichols  
Well Plugging Supervisor