

1571-20011-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Yucca Petroleum Company,

Complete Address: P.O. Box #2585, Amarillo, Texas.

Lease Name Wright Well No. 1

Location CNW-SE Sec. 32 Twp. 18 Rge. (E) (W) 32

County Scott Total Depth 1750'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Ks. License No. _____

Operation Completed: Hour 9:00 PM Day 11 Month 12 Year 1968

The Above well was plugged as follows:

335'--8 5/8" Surface casing, cement circulated with 280 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1285' and displaced 100 Sx. cement thru
DP from 1285' to 960'. Pulled DP to 360' and displaced 20 Sx. cement thru DP from
360' to 300'. Pulled DP, set bridge @ 40' with 1/3 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

RECORDED
DATE 12/17/68
ENV. NO. 9044-W