

K  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson Oil Producer  
Complete Address 408 One Twenty Bldg., Wichita, Kansas  
Lease Name Grube "A" Well No. 1  
Location NW ~~SE~~ ~~NE~~ NW NESE Sec. 24 Twp. 18 Rge. (E) (W) 32  
County Scott Total Depth 4315'  
Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Sargent Pipe Pulling  
Address Liberal, Kansas License No. 511  
Operation Completed: Hour 2 P Day 2 Month 7 Year 1974

The above well was plugged as follows:  
RTD 4315' 8 5/8 csg set at 674' cwc 350 sk.  
4 1/2" csg set at 4314' cw 150 sk cmt.  
Pumped 20 sk cmt plug down 4 1/2 csg -top of cement 3280'.  
Cutoff and recovered 3022' of 4 1/2 csg.  
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug  
and pumped 70 sk cmt -displaced with 15 sk gel & water & capped with 30 sk cmt by  
Hallib. Cem. Co.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 7/10/74  
INV. NO. 9471-W