

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3
6-4-68
RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1972
5-15-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Beckley Well No. A-1

Location NE-SW-SW Sec. 24 Twp. 18 Rge. (E) (W) 32

County Scott Total Depth 4605'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Bldg., Wichita, Ks. License No.

Operation Completed: Hour 8:30 PM Day 10 Month 5 Year 1972

The above well was plugged as follows:

678'--8 5/8" Surface casing, cement circulated with 525 Sx.
Top of Dakota section @ 860'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement
thru DP from 1050' to 725'. Pulled DP to 710' and displaced 30 Cu. Ft. cement thru
DP from 710' to 635'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Dehler*
Well Plugging Supervisor

DATE 5-15-72

INV. NO. 5711-W