

15-17120037-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 26 1972
7-26-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Incorporated,
Complete Address Box #18407, Wichita, Kansas.
Lease Name Strickert Well No. 1
Location SE-NE-SW Sec. 36 Twp. 18 Rge. (E) (W) 32
County Scott Total Depth 4730'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Company, Incorporated,
Address Box #405, Chase, Kansas. License No. 624
Operation Completed: Hour 3:00 PM Day 24 Month 7 Year 1972

The above well was plugged as follows:

668'--8 5/8" Surface casing, cement circulated with 400 Sx.
3022'--5 1/2" Production casing cemented on bottom with 150 Sx. Top of cement @ 2416'
(Temperature Survey). Well plugged back to 2810', Top of perforations @ 2770'.
Sanded well back to 2750' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
(2800') and squeezed well initially with 5 sacks hulls and 14 sacks gel and followed
with 110 Cu. Ft. cement from 1275' to 950' then 7 sacks gel from 950' to 675' and
followed with 30 Cu. Ft. cement from 675' to 600' then 14 sacks gel from 600' to 40'
and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-
900#. Final shut-in pressure-500#. (Mudding and cementing by Globe Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 7-28-72
INV. NO. 6074-10