

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAR 1 - 1962
3-15-62
CONSERVATION DIVISION
WICHITA, KANSAS

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Saline

Location: S3- SE- S3- Sec. 24- Twp. 15 Rge. 4 (EX) (W)

Name of Field: Unknown Total Depth: 3407'

I have this date completed supervision of plugging of:

Lease Name: Dahlsten Well No. I

Operator's Full Name: Quality Supply Co.

Complete Address: 701 Union Nat. Bldg. Wichita, Kansas

Plugging Contractor R & D- Casinr Pulling Co.

Address: P.O. box 569 Ellinwood, Kansas License No. 236

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 5:PM Day 10 Month 3 Year 62

The above well was plugged as follows:

Filled hole w/ sand from T.D. 3407' back to 3390' ran 5 sack cement w/ dump bailer.
Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 3315' back to 325' set 15'
rock bridge and ran 4 vds of ready mix cement from 310' back to zero 5' below ground
level. 10 3/4" surface pipe 5' below ground level.

Signed: Carl M. Jones
Conservation Division Agent

Reviewed: Harold Hallis
Field Supervisor

Remarks:

INDEXED
DATE 3/30/62
REV. NO. 4915-4