

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Saline

County. Sec. 24 Twp. 15 Rge. 4 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE SW

Lease Owner Studnicka and Vaughn (Honaker Drlg. Co., Inc.)

Lease Name Carlson Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 7-17 19 51

Application for plugging filed 7-17 19 51

Application for plugging approved 7-17 19 51

Plugging commenced 7-17 11 P.M. 19 51

Plugging completed 7-18 A.M. 19 51

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production ----- 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruhl Durkee

Producing formation Depth to top Bottom Total Depth of Well 3434 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	347	None
				Cemented	250 sacks	Circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy Mud.

Set bridge at 220 ft. 15 sacks cement.

Filled hole with Mud to 10 ft. of top of hole

Set plug w/ 5 sacks cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to \_\_\_\_\_ Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Barton Sedgewick, Honaker Drilling Co., Inc. (contractor)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. Squires

SUBSCRIBED AND SWORN to before me this 2nd day of August 1951

(Address) Seward S. Freidly  
Notary Public.

My commission expires My Commission Expires Jan. 31, 1953

FILE SEC 24 T 15 R 4  
BOOK PAGE 96 LINE 9

15169-00656-0000

### Drillers Log

Carlson #1

W. E. Studnicka and P. F. Vaughn

Top Soil and Shale	0	45
Shale	45	110
Sand	110	115
Shale and Shells	115	309
Anhydrite	309	340
Shale and Shells	340	347
Run 12 joints 8 5/8" surface casing at 347 ft. - cemented with 250 sacks cement		
Shale and Shells	347	500
Grey Sandy Shale	500	525
Blue Shale and Shells	525	560
Shale and Lime	560	575
Shale and Shells	575	635
Lime and Shale	635	900
Shale and Lime Shells	900	1280
Salt and Shale	1280	1370
Shale and Lime	1370	1630
Shale and Lime	1630	1880
Shale and Lime	1880	2645
Lime	2645	2675
Shale	2675	2715
Lime and Shale	2715	3000
Lime and Shale	3000	3030
Lime	3030	3065
Lime and Shale	3065	3085
Cherty Lime and Shale	3085	3150
Lime and Shale	3150	3215
Shale	3215	3350
Lime and Shale	3350	3434 T.D.

C  
O  
P

The above is correct to the best of my knowledge.

HONAKER DRILLING COMPANY, INC.

By Joe J. Honaker  
President

Subscribed and sworn to before me this 17th day of July 1951

My commission expires: June 25, 1955

Notary Public  
Barton County, Kansas

PLUGGING  
KAS SEC 24 T 15 R 2W  
BOOK PAGE 96 LINE 9

RECEIVED  
AUG 2 X 1951  
CONSERVATION DIVISION  
Wichita, Kansas