

15167-0000  
00489


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Saline County. Sec. 25 Twp. 15 Rge. 4 W (E) (W)  
Location as "NE/CNW/SW" or footage from lines C SE SW  
Lease Owner Arvel Smith  
Lease Name Frest Well No. 3  
Office Address Rt. 1 Towanda, Kansas 67144  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 3-29 19 53  
Application for plugging filed 6-10 19 72  
Application for plugging approved 6-11 19 72  
Plugging commenced 7-13 19 72  
Plugging completed 7- 19 72  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott  
Producing formation Depth to top Bottom Total Depth of Well 3457' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2838'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3457' to 3490'. Dumped 5 ex of cement. Mudded hole to 215'. Made 10' of rack bridge. Dumped 4 Yrds. of Ready-Mix Cement, filling to the bottom of the collar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 24 1972  
7-24-72  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.  
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb  
2809 King St. Hutchinson, Kansas 67501  
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of July, 1972

Judy Lamb  
Notary Public.

My commission expires January 5, 1974

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-169-~~00486~~ 0000  
COPY

Company- REPUBLIC NATURAL GAS COMPANY  
Farm- Frost No. 3

25  
SEC. 25 T. 16 R. 4W  
C SE SW

Total Depth. 3457  
Comm. 3-15-53 Date 3-29-53  
Shot or Treated.  
Contractor. E. K. Carey  
Issued. 12-5-53

County Saline  
KANSAS



CASING:  
10 3/4" 365' oem. w/250 sx  
5 1/2" 3457' oem. w/62 sx

Station. 1303' KB

Production. 180 BO & trace wtr

Figures indicate Bottom of Formations. K. B.

Form. K.B.	
clay & shale	30
sand	35
shale	47
sand	55
shale & lime	80
shale & shells	250
sand	253
lime shale	350
lime	525
lime & shale	1180
shale & shells	1720
lime & shale	1825
lime	1925
shale & lime	2237
lime K. C.	2265
lime	2595
shale & lime	2745
shale & shells	2860
shale & lime	2948
lime	3175
lime & shale	3260
shale	3380
shale & lime	3412
lime-Viola-Maquoketa	3418
lime	3457
Total Depth	

SCOUT TOPS: (SCHLUMBERGER)

Kindershook	3147
Misonor	3315
Hunton	3318
Maquoketa Shale	3335
Viola	3406

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1972  
CONSERVATION DIVISION  
Wichita, Kansas