


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 25 Twp. 15 Rge. (E) 4 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4 NW/4 NE/4
Lease Owner Musgrove Petroleum Corporation (Operator)
Lease Name Swenson Well No. 2
Office Address 407 K.F.H. Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Lost Hole
Date well completed June 15 19 51
Application for plugging filed June 15 19 51
Application for plugging approved June 15 19 51
Plugging commenced June 15 19 51
Plugging completed June 15 19 51
Reason for abandonment of well or producing formation Lost Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, Box 597, McPherson, Kansas
Producing formation Depth to top Bottom Total Depth of Well 410' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	165'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 165'.
Set a wooden plug at 165' and filled w/ 15 sacks of cement.
Set second plug at 15' and filled w/ 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corp.
Address 407 K.F.H. Bldg.
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
407 K.F.H. Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of June, 19 51.

Notary Public.

My commission expires December 5, 1951

PLUGGING
FILE SEC 25 T 15 R 4
BOOK PAGE 89 LINE 5

6-21-51

CONTRACTOR'S WELL LOG

COMPANY: Musgrove Petroleum Corporation
 CONTRACTOR: Victor Drilling Company
 FARM: Swenson No. 2
 LOCATION: NE/4 NW/4 NE/4, Sec. 25-T15S-R4W
 Saline County, Kansas.
 COMMENCED: June 10, 1951
 COMPLETED: June 15, 1951

0	8	Soil
8	20	Shale
20	50	Sand
50	70	Shale
70	300	Sand and gravel
300	350	Lime
350	410	Shale
	410	Rotary Total Depth

Set 165' of 8-5/8" surface casing, cemented with 150 sacks.
 Lost Hole.

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Swenson #2, Sec. 25-15S-4W, Saline County, Kansas, as reflected by files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION
 By Gordon L. Koelling
 Secretary

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 19th day of June, 1951.

Madeline J. Jissel
 Notary Public

My commission expires: 12/5/51

PLUGGING
 FILE SEC. 25 T. 15 R. 4W
 PAGE 89 LINE 3