

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County, Sec. 25 Twp. 15 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW NE

Lease Owner Knight Casing Pulling Company

Lease Name Swenson Well No. 5

Office Address Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 2-13-63 19

Plugging completed 2-14-63 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3414 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	335'	None
				4-1/2"	3413'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to packer set @ 2165' and dumped 3 sacks of cement with dump bailer. Pulled 4 1/2" casing. Set rock bridge from 200' to 190' and ran 20 sacks of cement. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

FEB 25 1963
2-25-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss. Noel J. Knight

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 1963

Milton J. Volin Notary Public.

My commission expires May 20, 1964

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Mendota, Wichita, Kansas


15-169-00849-0000

Company- MUSGROVE PETRO. CORP.
Farm- Swenson No. 5

SEC. 25 T. 15 R. 4W
SW NW NE

Total Depth. 3414
Comm. 2-18-52 Comp. 3-4-52
Shot or Treated.
Contractor. Musgrove Petro. Corp.
Issued. 6-7-52

County Saline
KANSAS



CASING:
8 5/8" 335' com. w/300 sx
4 1/2" 3413' com. w/75 sx

Elv. Den. 1395

Production. 143 BO & 10% wtr.

Fig. 1.1. Waste Pattern of Farm. No. 5.

clay	25
sand	50
sandy shale	100
shale & shells	255
sand, shale & shells	275
sand & shale	330
anhydrite	405
anhydrite & shale	440
shale & shells	495
lime & shale	574
red rock	600
shale & lime	735
shale & shells	885
lime	1035
shale & lime	1070
shale & shells	1255
shale	1585
shale & shells	1605
shale & lime	1950
shale & shells	2070
lime & shale	2215
shale & shells	2400
shale & lime	2720
shale	2815
shale & lime	2975
shale	3065
lime, shale & chert	3107
lime	3130
lime & shale	3150
chat, shale & lime	3255
shale & lime	3360
shale & shells	3414RTD
Total Depth	

Scout Tops:
Misenor 3320
Hunton 3324
Maquoketa Dolomite 3412
Viola 3414

SHINE COMPANY

FEB 25 1953

CONSERVATION