


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines _____
_____ Saline County. Sec. 25 Twp. 15 Rge. 4 W (E) _____ (W)
Location as "NE/CNW/SW" or footage from lines _____ SW SW SW
Lease Owner Arvel Smith
Lease Name Frost Well No. I
Office Address Rt. 1 Towanda, Kansas 67144
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 8-23 19 51
Application for plugging filed 6-10 19 72
Application for plugging approved 6-11 19 72
Plugging commenced 7-10 19 72
Plugging completed 7-20 19 72
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3425' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		3005'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3425' to 3400'. Dumped 3 sq of cement. Mudded hole to 215'. Made 10' of rock bridge. Dumped 3 Yrds. of Ready-Mix Cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1972
7-24-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 21 day of July, 1972

Judy Lamb
Notary Public.

My commission expires January 5, 1974

COPY


Company- E K CAREY
 Farm- Willie Frost No. 1

SEC. 25 T. 15 R. 4W
 SW SW SW

Cable Tool - 3425'

Total Depth. 3415
 Comm. 8-10-51 Date 8-23-51
 Shot or Treated.
 Contractor. E K Carey
 Issued. 10-20-51

County Saline KANSAS



CASING:

8 5/8" 335' cem w/250 sxs.
 4 1/2" 3417.75' cem w/75 sxs.

Elevation. 1300 DE

Production. DD 1865 bbls.

Figures indicate Bottom of Formations.

rotary base & collar	8
clay	35
sand	45
shale	100
shale, shells	270
lime, shale	335
lime	380
lime, shale	695
lime	935
shale, limo	1495
shale, shells	1668
limo	1755
shale, limo	2225
shale	2251
limo	2610
shale	2655
shale, limo	2906
lime	3163
shale	3265
shale, limo	3326
limo	3340
shale	3413
lime Maquoketa dolo.	3415
Total depth	

Tops:	
Mississippi lime	2905
Kinderhook shale	3162
Misner sand	3322
Hunton	3324
Maquoketa shale	3343
Maquoketa dolomite	3413

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 12 1972
 CONSERVATION DIVISION
 Wichita, Kansas