



15-053-20301-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

October 23, 1972

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1972
10-27-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Albert ^{BORELL} Berrel

Complete Address: Box 391, Wilson, Kansas 67490

Lease Name: Kepka Well No. 1

Location: C NE NE NE Sec. 28 Twp. 14 Rge. 10 (E) (W) X

County: Ellsworth Total Depth 2910' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and
cement hole with 25 sacks cement through drill pipe. Fill hole with
mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent